

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

KCC Pkt
GPS TAGS
4811

API Well Number: 15-077-20196-00-00
Spot: ~~W2121E~~
Sec/Twnshp/Rge: 12-34S-9W
660 feet from ~~S~~ Section Line, 1140 feet from E Section Line
Lease Name: HUGHBANKS-MILLER GAS Unit Well #: 1-12
County: HARPER Total Vertical Depth: 4608 feet

Operator License No.: 31191
Op Name: R & B OIL & GAS, INC.
Address: 904 N. LOGAN PO BOX 195
ATTICA, KS 67009

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4594	2890	175 SX CMT Pkt
SURF	8.625	269	-	225 SX CMT # 149.76

Well Type: GAS UIC Docket No: Date/Time to Plug: 03/09/2007 9:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: OPEN HOLE 4594-4608 SAND 50' ABOVE OPEN HOLE. CAP W/4 SXS CMT. 35 SXS @ 1400', 35 SXS @ 850', CIRC. CMT FROM 320' TO SURFACE. AS KCC REQUIRES.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/09/2007 11:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

OPEN HOLE FILLED WITH SAND TO 4540' AND CAPPED WITH 4 SKS OF CEMENT. CASING WAS RECOVERED FROM 2890', AND PULLED TO 1400', WHERE 35 SKS OF CEMENT WAS SPOTTED. CASING WAS PULLED TO 850', WHERE 35 SKS OF CMT WAS SPOTTED. CASING WAS PULLED TO 320' CEMNT WAS CIRC. TO SURFACE, PULLED REMAINING CASING AND TOPPED OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
4608			
4594	4608		


INVOICED

DATE 4-27-07
INV. NO. 2007061664

Remarks:

Plugged through: CSG

District: 02

Signed 

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 19 2007

CONSERVATION DIVISION
WICHITA, KS



