

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-079-20395-00-00  
Spot: S2SE Sec/Twnshp/Rge: 2-23S-3W  
593 feet from S Section Line, 1496 feet from E Section Line  
Lease Name: RATZLAFF Well #: 1  
County: HARVEY Total Vertical Depth: 3288 feet

Operator License No.: 5399  
Op Name: AMERICAN ENERGIES CORPORATION  
Address: 155 N. MARKET, STE 710  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3287		100 SX
SURF	8.625	424		225 SX

# 106,86

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/30/2007 1:00 PM  
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION  
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method: C.I.B.P. @ 3240'. Sand to 3,175' & top with 4 sxs. cement. Rip 5 1/2" casing & pull same. Run tubing to 475' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/02/2007 2:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 3,168' & topped with 4 sxs. cement. Ripped 5 1/2" casing @ 1,304' & pulled same. Ran 2 3/8" tubing to 491' & pumped 5 1/2 yds. slurry mix - did not circulate to surface. Ran tubing & tagged cement @ 271' Pulled tubing to 270' & pumped 3 1/3 yds. slurry mix - did not circulate to surface. Ran tubing & tagged cement @ 120'. Pulled tubing to 119' & circulated 2 1/2 yds. slurry mix to the surface. Checked top plug @ 4:00 p.m. & cement at surface.

Perfs:

Top	Bot	Thru	Comments
3224	3232		UPPER WARSAW

**INVOICED**  
DATE 4-26-07  
INV. NO. 200 7061651

Remarks: USED SLURRY MIX BY MCPHERSON CONCRETE. INVOICE # 56712, # 56724, & # 56730.

Plugged through: TBG

District: 02

Signed Michael Wilson  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS

PRT