

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-01321-00-00
Spot: SWNWNE Sec/Twnshp/Rge: 6-24S-5E
4198 feet from S Section Line, 2311 feet from E Section Line
Lease Name: ARTHUR Well #: 1
County: BUTLER Total Vertical Depth: 2453 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2445		
SURF	8.625	105		

79.72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/21/2007 8:00 AM
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.
Proposal Rcvd. from: STEVE KILE Company: BUCKEYE CORP. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC REG.

Plugging Proposal Received By: _____ Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/22/2007 4:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

3/21/07 RIH W/TBG @2433', LODED HOLE W/ WATER, ESTABLISHED CIR. MIXED & PUMPED 30 SKS OF CEMENT CLASS A W/ 2% CC. WAITED 2 HRS, RIH W/TBG @ 2309' CIRCULATE HOLE CLEAN. HAD CEMENT RETURNS. 3/22/07 SHOT 5.5" CASING @ 980'. PULLED W/32 JTS 5.5 CASING. RIH W/TBG @ 308' MIXED & PUMPED 200 SKS 60/40 POZMIZ 4% GEL TO SURFACE

Perfs:

Top	Bot	Thru	Comments
2445	2453		

INVOICED
DATE 4-26-07
INV. NO. 2007061652

Remarks: HURRICANE WELL SERVICE TICKET # 1799

Plugged through: TBG

District: 02

Signed _____

Duane Krueger

(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 19 2007

CONSERVATION DIVISION
WICHITA, KS

M

PK