

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-01326-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 6-24S-5E *KCC PKT GPS Figs*  
2902 feet from S Section Line, ~~1113~~ feet from E Section Line  
Lease Name: ARTHUR *2313* Well #: 7  
County: BUTLER Total Vertical Depth: 2513 feet

Operator License No.: 5387  
Op Name: THE BUCKEYE CORPORATION DBA A  
Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2482		
SURF	8.625	121		

*\$ 81.67*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/23/2007 8:00 AM  
Plug Co. License No.: 32006 Plug Co. Name: HURRICANE WELL SERVICE, INC.  
Proposal Rcvd. from: STEVE KILE Company: BUCKEYE CORP. Phone: (316) 321-3800

Proposed Plugging Method: AS PER KCC REG.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 03/26/2007 1:45 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

3023-07 RIH W/TBG @ 2462 ESTABLISHED CIR. MIXED AND PUMPED 25 SKS CLASS A W/2% CC. WAITED 2 HRS. RIH W/TBG @ 2245. CIR. HOLE CLEAN HAD CEMENT RETURNS. 3-26-07 SHOT 5.5" CASING @ 1190', RECOVERED 38 JTS 5.5" CASING. RIH W/ TBG @ 308'. ESTABLISHED CIRCULATION MIXED AND PUMPED 165 SKS OF CEMENT WHICH CIR. TO SURFACE.

Top	Bot	Thru	Comments
2482	2492		

**INVOICED**  
DATE 4-26-07  
INV. NO. 2007061052

Remarks: HURRICANE WELL SERVICE TICKET# 1812 CEMENT 60/40 POZMIX W/4% GEL

Plugged through: TBG

District: 02

Signed *Duane Krueger*  
(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS