

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-01345-00-00

Spot: NWNENW

Sec/Twnshp/Rge: 6-24S-5E

KCC PDN  
GPS Figs

4880 ~~4835~~ feet from S Section Line, 3010 feet from E Section Line

Lease Name: CLAASSEN

3650 Well #: 9

County: BUTLER

Total Vertical Depth: 2473 feet

Operator License No.: 5387

Op Name: THE BUCKEYE CORPORATION DBA A

Address: PO BOX 1020  
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	2460		
STRL	10.5	119		

\$ 80.37

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/28/2007 11:00 AM

Plug Co. License No.: 32006

Plug Co. Name: HURRICANE WELL SERVICE, INC.

Proposal Rcvd. from: STEVE KILE

Company: AZTEC CO

Phone: (316) 321-3800

Proposed  
Plugging  
Method:

AS PER KCC REG.

Plugging Proposal Received By: DUANE KRUEGER

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/30/2007 4:00 PM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

3-28-07 RIH W/TBG @ 2415', MIXED & PUMPED 40 SKS CLASS A W/2% CC. WAITED 2 HRS. RIH WITH TBG @ 2233' CIRCULATED HOLE CLEAN. HAD CEMENT IN RETURNS. LAYED DOWN 15 JTS. (460') 5.5" CSG W/7"X5.5" PACKER. 3-30-07 SHOT 7" @ 993', LAYED DOWN 31 JTS. 7" CSG.. RIH W/TBG @ 275', MIXED AND PUMPED 185' SKS 60/40 POZMIX 4% GEL CIRCULATED TO SURFACE.

INVOICED

DATE 4-26-07

INV. NO. 2007061652

Remarks: OH 2460-63' PBTD 2463 HURRICANE CEMENTING CO. TICKET # 1814

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION

Form CP-2/3

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS

M

MS