

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-01149-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 24-30S-8W
330 feet from S Section Line, 330 feet from W Section Line
Lease Name: WEST SPIVEY UNIT Well #: 7
County: KINGMAN Total Vertical Depth: 4385 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 13727 NOEL RD., STE 500
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	4384		200 SX
SURF	10.75	197		250 SX. \$ 142.51

Well Type: OIL UIC Docket No: Date/Time to Plug: 02/16/2007 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: Phone: (620) 727-3410

Proposed Plugging Method: SAND 50' ABOVE THE PERFS. CAP WITH 7 SKS CMT. RECOVER CASING. SPOT 50 SKS CMT AT 1250'. SPOT 50 SKS CMT AT 700', CIRC. CMT FROM 350' TO SURFACE.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE
Date/Time Plugging Completed: 02/16/2007 2:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

WELL WAS SANDED BACK TO 50' ABOVE PERF. 4242', CAPPED WITH 7 SKS CMT. NO STRECH, NO RCOVERY OF CASING. 1250' SQUEEZED 50 SKS CMT. PERF. CASING @ 700', SQUEEZES 50 SKS CMT.. PERF. CASING @ 250' CIRC. CMT. TO SURFACE, PULLED CASING. TOPPED OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
4292	4385		MISSISSIPPI

INVOICED
DATE 4-27-07
INV. NO. 2007061659

Remarks: ALLIED CMTG #32410 COMM 3% CACL

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

RECEIVED KANSAS CORPORATION COMMISSION Form CP-2/3

APR 19 2007

CONSERVATION DIVISION WICHITA, KS