

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-20616-00-00
Spot: N2SESW Sec/Twnshp/Rge: 13-30S-8W
710 feet from S Section Line, 1980 feet from W Section Line
Lease Name: WEST SPIVEY UNIT Well #: 1
County: KINGMAN Total Vertical Depth: 4350 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY
Address: 13727 NOEL RD., STE 500
DALLAS, TX 75240

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| PROD | 5.5 | 4315 | 3430 | 100 SX |
| SURF | 8.625 | 250 | | 250 SX |

\$ 141.38

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2007 9:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (972) 727-3410

Proposed
Plugging
Method:

sand 50' above perfs. Cap with 5 sks of cmt. 35 sks at 1250', 35 sks at 750' circ. cmt. to surface.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 01/05/2007 1:00 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs were covered with sand to 4210' and capped with 5 sks of cmt. Casing was recovered from 3420' and pulled to 1250' where 35 sks of cmt. was spotted. Pulled casing to 750' spotted 35 sks cmt.. Pulled casing to 300', circ. Cmt to surface with 140 sks cmt..

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 4264 | 4293 | | MISSISSIPPI |

INVOICED
DATE 4-27-07
INV. NO. 2007061659

Remarks: ALLIED CMT. CO. 60/40 POZMIX 4% GEL

Plugged through: CSG

District: 02

Signed _____

(TECHNICAL) RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

M

PGT