

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: ⁰¹ 15-095-00346-00-00
Spot: SWNE Sec/Twnshp/Rge: 18-29S-7W
3300 feet from S Section Line, 1980 feet from E Section Line
Lease Name: BELT Well #: 1
County: KINGMAN Total Vertical Depth: 4538 feet

Operator License No.: 4706
Op Name: MESSENGER PETROLEUM, INC.
Address: 525 S. MAIN ST.
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	4287		175 SX
SURF	8.625	250		150 SX

147.49

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 01/24/2007 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: 15 SKS ON BOTTOM, 35 SKS @ 1200', 34 SKS @ 700', CIRC CMT FROM 300' TO SURFACE

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 01/24/2007 12:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:
A 15 SK PLUG WAS PUMPED DOWN TUBING TO PLUG BOTTOM PERFS.. THE TUBING WAS PARTED AT 1250'. ONE JOINT WAS PULLED AND 35 SKS. OF CEMENT WAS SPOTTED IN PLACE. THE TUBING WAS PULLED TO 700' WHERE 35 SKS OF CMT. WAS SPOTTED. TUBING WAS PULLED TO 300' AND CMT WAS CIR. TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
4109	4129		MISS

INVOICED
DATE 4-27-07
INV. NO. 2007061660

Remarks: ALLIED CMTG 60/40 POZMIX 4% GEL
Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 19 2007

CONSERVATION DIVISION
WICHITA, KS

[Handwritten mark]

[Handwritten mark]