

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-22033-00-00  
Spot: NENWSENE Sec/Twnshp/Rge: 33-30S-7W  
1450 feet from N Section Line, 800 feet from E Section Line  
Lease Name: WELLS Well #: Z-1  
County: KINGMAN Total Vertical Depth: 4800 feet

Operator License No.: 4706  
Op Name: MESSENGER PETROLEUM, INC.  
Address: 525 S. MAIN ST.  
KINGMAN, KS 67068

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4800		250 SX CMT.
SURF	8.625	222		225 SX CMT. <b>\$156.00</b>

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 532-5400

Proposed Plugging Method: AS KCC REQUIRES.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: NONE  
Date/Time Plugging Completed: 01/23/2007 12:30 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

PERFS COVERED WITH SAND FROM TD TO 3940' AND CAPPED WITH 4 SKS OF CMT.. CASING WAS RECOVERED FROM 3440' AND PULLED TO 1100' WHERE 35 SKS OF CMT. WAS SPOTTED. CASING WAS PULLED TO 700' WHERE 35 SKS OF CMT WAS SPOTTED. THE CASING WAS PULLED TO 275' WHRE CMT WAS CIRC. TO SURFACE. PRODUCTION CASING PULLED AND WELL TOPPED OFF WITH CEMENT.

Perfs:

Top	Bot	Thru	Comments
4354	4362		MISS
4012	4016		HERTHA

**INVOICED**  
DATE 4-27-07  
INV. NO. 2007061660

Remarks: ALLEID CEMENTING CO. TICKET # 60/40 POZMIX 4% GEL.

Plugged through: CSG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION CP-2/3

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS