

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-17621-00-00

Spot: E2SW

Sec/Twnshp/Rge: 19-27S-10W

1320 feet from S Section Line, 3300 feet from E Section Line

Lease Name: CUNNINGHAM UNIT B

Well #: 1

County: KINGMAN

Total Vertical Depth: 3605 feet

Operator License No.: 3880

Op Name: KC RESOURCES, INC. DBA CRYSTAL R

Address: P. O. BOX 6749

SNOWMASS VILLAGE, CO 81615

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	7	3449		
------	---	------	--	--

SURF	12.5	341		
------	------	-----	--	--

117.16

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/02/2007 2:00 PM

Plug Co. License No.: 33695

Plug Co. Name: MID-KAN WELL SERVICE, LLC

Proposal Rcvd. from: JACK LUTHI

Company: KC RESOURCES, INC.

Phone: (620) 770-2375

Proposed
Plugging
Method:

Sand or cmt. 50' above perms, rec. pipe, 50 sks 1500' circ cmt from 600' to surface

Plugging Proposal Received By: DOUG LOUIS

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 02/07/2007 11:00 AM

KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

Casing parted @1526', holes in casing above partng. Hole in casing 400'-600'. Iron in hole couldn't get any deeper than 1526'. Ran 2 7/8" tubing to 1526' and spotted 50sks cmt. SDFN. 2/3/07 Tagged cmt. with tubing at 1340'. Pulled tubing to 600', pumping cmt., cmt. Circ. on insdie of 7" casing (125 sks). Pulled tubing and shut down. Dug out braden head and cut off. 2/7/07 Ran 1" tubing to 600' and circ. Cmt. to surface.

INVOICED

DATE 4-26-07


INV. NO. 2007061653

Remarks: JET STAR CMT. CO. COMMON & 60/40 POZMIX 4% GEL

Plugged through: TBG

District: 02

Signed



(TECHNICIAN) RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2007

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

