

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-035-19220-00-00
Spot: SESESW Sec/Twnshp/Rge: 17-33S-3E
393 feet from S Section Line, 3079 feet from E Section Line
Lease Name: WEST RAINBOW BEND UNIT Well #: 16
County: COWLEY Total Vertical Depth: 3671 feet

Operator License No.: 33608
Op Name: W.D. SHORT OIL CO., LLC
Address: 102 S. RIVER ROAD PO BOX 729
OXFORD, KS 67119

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3324	590	150 SX CMT
SURF	8.625	180		175 SX CMT \$ 119.31

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/02/2007 8:00 AM
Plug Co. License No.: 32475 Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C
Proposal Rcvd. from: DUANE KRRUGER Company: KCC Phone: (316) 630-4000

Proposed Plugging Method: PER KCC REGS.

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL
Date/Time Plugging Completed: 02/22/2007 12:30 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

1/2/07 RIH W/TBG @ 3250', 1/3/07 MIXED PUMPED 40 SKS CEMENT, WAITED 2 HRS. TAGGED CEMENT AT 2900', SHOT OFF 5.5 " @590', POOH W 5.5 " CSG 02/22/07 RIH W/TBG @ 360' CONSOLIDATED ESTABLISHEDS CIRCULATION, MIXED & PUMPED 190 SKS.

Perfs:

Top	Bot	Thru	Comments
3217	3239		

INVOICED
DATE 4-30-07
INV. NO. 2007061669

Remarks: 60/40 POZMIX 4% GELL CONSOLIDATED TICKET #16878

Plugged through: TBG

District: 02

Signed Duane Krueger
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION
Form CP-2/3

APR 19 2007

CONSERVATION DIVISION
WICHITA, KS

m

PKT