

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-155-21423-00-00
Spot: NWNESW Sec/Twnshp/Rge: 11-25S-9W
2278 feet from S Section Line, 3763 feet from E Section Line
Lease Name: BIGGERSTAFF Well #: 6-11
County: RENO Total Vertical Depth: 3980 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3980	<u>3026</u>	100 SX
SURF	8.625	179		175 SX

\$ 129.35

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/16/2007 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 234-5191

Proposed Plugging Method: SAND BACK TO 3800' AND CAP W/ 5 SKS CMT., 35 SKS @ 1400, 35 SKS @ 800', @ 250' CIR. CMT. TO SURFACE.

Plugging Proposal Received By: MICHAEL WILSON Witness Type: PARTIAL
Date/Time Plugging Completed: 03/19/2007 8:00 AM KCC Agent: BILLIE J. HOPE

Actual Plugging Report:

SANDED BACK TO 3700', CAPPED WITH 5 SKS. SHOT CASING AT 3027 PULLED TO 1400', PLACED 35 SKS OF CEMENT AND 50 LBS. HULLS. PULLED CASING TO 800' PLACED 35 SKS OF CEMENT AND 50 LBS HULLS. CASING PULLED TO 260' CIRCULATED 125 SKS OF CEMENT AND 100 LB HULLS WITH CEMENT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3859	3867		

INVOICED
DATE 4-30-07
INV. NO. 200706/666

Remarks: COPELAND CEMENT CO. TICKET# CO31660

Plugged through: CSG

District: 02

Signed [Signature]
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 19 2007

CONSERVATION DIVISION
WICHITA, KS

[Signature]

[Signature]