

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-22533-00-00
Spot: ~~E2E2E2~~ ^{sesene}
Sec/Twnshp/Rge: 31-18S-10W
2550 feet from N Section Line, 100 feet from E Section Line
Lease Name: NOVONTY ET AL Well #: 1-31
County: RICE Total Vertical Depth: 3320 feet

Operator License No.: 3882
Op Name: SAMUEL GARY JR. & ASSOCIATES, IN
Address: 1670 BROADWAY #3300
DENVER, CO 80202

String Size Depth (ft) Pulled (ft) Comment
SURF 8.625 343

\$107.90

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 03/23/2007 7:00 AM
Plug Co. License No.: 30141 Plug Co. Name: SUMMIT DRILLING COMPANY
Proposal Rcvd. from: DAN Company: SUMMIT DRILLING COMPANY Phone: (620) 343-3278

Proposed Plugging Method: 35 SKS TOP OF ARBUCKLE, 35 SKS @ 1250', 35 SKS @ 850', 35 SKS @ 393", 25 SKS @60', 15 SKS RH, 10 SKS IN MH.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: NONE
Date/Time Plugging Completed: 03/23/2007 9:00 AM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:


DRILL PIPE WAS RUN OPEN HOLE TO TOP ARBUCKLE@ 3240 WHERE 35SKS WERE SPOTTED. PIPE WAS PULLED TO 1250' WHERE 35 SKS WAS SPOTTED, DRILL PIPE WAS PULLED TO 850' WHERE 35 SKS WAS SPOTTED. DRILL PIPE PULLED TO 393' 35 SKS OF CEMET WAS SPOTTED. DRILL PIPE WAS PULLED TO 60' AND 25 SKS CMT. WAS CIR. TO SURFACE.

INVOICED
DATE 4-30-07
INV. NO. 2007061667

Remarks: JET STAR TICKET #16145 60/40 POZMIX W 4% GEL

Plugged through: DP

District: 02

Signed 
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

APR 19 2007

CONSERVATION DIVISION
WICHITA, KS

W

PET