

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-02193-00-00  
Spot: NENENW Sec/Twnshp/Rge: 11-34S-5E  
330 feet from N Section Line, 2310 feet from W Section Line  
Lease Name: JESSE RAHN Well #: 1  
County: COWLEY Total Vertical Depth: 3171 feet

Operator License No.: 6679 33608

String Size Depth (ft) Pulled (ft) Comment

Op Name: SHORT, W.D. AND MARJORIE DBA W.

PROD 4.5 3155 1330 125 SX

102 S. River Rd, Po Box 729 W. D Short, Inc,  
Address: PO BOX 1

SURF 8.625 224 175 SX

OXFORD, KS 67119

KCC ACT Per T-1 4/26/07

# 103.06

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 02/06/2007 12:00 AM

Plug Co. License No.: 32475

Plug Co. Name: BRADEN, JAMES R. DBA BRADEN PETROLEUM & WELL PLUGGING C

Proposal Rcvd. from: JIM BRADEN

Company: B.P.C/ WELL PLUGGING

Phone: (620) 222-1252

Proposed Plugging Method: PER KCC INSTRUCTION.

Plugging Proposal Received By: DUANE KRUEGER

WitnessType: PARTIAL

Date/Time Plugging Completed: 03/15/2007 12:00 AM

KCC Agent: DUANE KRUEGER

Actual Plugging Report:

02/06/07 SANDED BACK ABOVE PERFS @ 3105', DUMP BAILED 4 SX CEMENT ON TOP. 02/07/07 SHOT 4.5 CSG @ 1330', LAYED DOWN 4.5 " CSG. 03/15/07 RIH W/TBG @275', B.P.C. WELL PLUGGING MIXED & PUMPED 98 SXS 60/40 POZMIX 4% GELL TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3155	3171		

Remarks: CEMENT TICKET # 07563

**INVOICED**  
DATE 4-30-07

INV. NO. 200706669

Plugged through: TBG

District: 02

Signed

Duane Krueger

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION Form CP-2/3

APR 19 2007

CONSERVATION DIVISION  
WICHITA, KS

*M*

*PRT*