

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20472-00-00
Spot: N2NWNE Sec/Twnshp/Rge: 31-18S-1E
4919 feet from S Section Line, 1958 feet from E Section Line
Lease Name: D RATZLAFF Well #: 31-2
County: MARION Total Vertical Depth: 2910 feet

Operator License No.: 5399
Op Name: AMERICAN ENERGIES CORPORATION
Address: 155 N. MARKET, STE 710
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2908		125 SX
SURF	8.625	198		175 SX

\$ 94.58

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 04/04/2007 9:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: DOUG WARD Company: AMERICAN ENERGIES CORPORAT Phone: (620) 628-4424

Proposed Plugging Method: Sand to 2,795' & top with 4 sxs. cement. Rip 4 1/2" casing & pull same. Run tubing to 250' & circulate cement to the surface.

Plugging Proposal Received By: MICHAEL WILSON WitnessType: NONE
Date/Time Plugging Completed: 04/05/2007 4:00 PM KCC Agent: MICHAEL WILSON

Actual Plugging Report:

Sanded to 2,785' & topped with 4 sxs. cement. Ripped 4 1/2" casing @ 1,371' & pulled same. Ran 2 3/8" tugging to 280' & circulated 6 yards slurry mix. 4/5/2007 Checked plug - cement down 80'. Ran tubing to 79' & circulated 3 yards slurry mix to the surface. 4/8/2007 Checked top plug - cement at 0'.

Perfs:

Top	Bot	Thru	Comments
2848	2855		

INVOICED

DATE 5/1/07
INV. NO. 2007061670

Remarks: USED SLURRY MIX BY BUILDER'S CONCRETE. INVOICE #3948 & #3949.

Plugged through: TBG

District: 02

RECEIVED
KANSAS CORPORATION COMMISSION

Signed

Michael Wilson

(TECHNICIAN)

APR 24 2007

CONSERVATION DIVISION
WICHITA, KS