

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-073-20084-00-00

Spot: NENESW

Sec/Twnshp/Rge: 26-25S-8E

2310 feet from S Section Line, 2310 feet from W Section Line

Lease Name: LADD

Well #: 7

County: GREENWOOD

Total Vertical Depth: 2592 feet

Operator License No.: 5697

Op Name: JACKSON BROS., L.L.C.

Address: 116 EAST THIRD ST.
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comment
--------	------	------------	-------------	---------

PROD	4.5	2555	752	75 SX CMT.
------	-----	------	-----	------------

SURF	7	111		35 SX CMT.
------	---	-----	--	------------

84.24

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 03/19/2007 8:00 AM

Plug Co. License No.: 5684

Plug Co. Name: SAGE, LARRY GEORGE

Proposal Rcvd. from:

Company:

Phone:

Proposed Plugging Method: 50' cement plug @ 2390', 50' cement plug @ 752', 256' cement plug to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

Witness Type: COMPLETE (100%)

Date/Time Plugging Completed: 03/21/2007 5:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

built rock bridge @ 2390', mixed & dumped 5 sxs. Cement with dump baler, shot casing @ 752' pumped 30 sxs. Cement pulled casing to 256' pumped 90 sxs cement to surface gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
2543	2544		
2426	2436		

RECEIVED
KCC DISTRICT #3

APR 16 2007 mH

CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2007

CONSERVATION DIVISION
WICHITA, KS

INVOICED

DATE 5-1-07

INV. NO. 2007061680

Remarks:

Plugged through: CSG

District: 03

Signed

Mike Heffern
(TECHNICIAN)

RECEIVED
KANSAS CORPORATION COMMISSION

APR 26 2007

CONSERVATION DIVISION
WICHITA, KS

PK