

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20779-00-00  
Spot: SEWSE Sec/Twnshp/Rge: 26-11S-34W  
1650 feet from S Section Line, 1650 feet from E Section Line  
Lease Name: SCHERTZ TRUST 'B' Well #: 1-26  
County: LOGAN Total Vertical Depth: 3050 feet

Operator License No.: 5003  
Op Name: MCCOY PETROLEUM CORPORATION  
Address: 8080 E. CENTRAL, SUITE 300  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	305		260 SX CMT.

\$ 99.13

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/31/2007 8:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: KEITH Company: MURFIN DRILLING CO., INC. Phone: (316) 267-3241

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE  
Date/Time Plugging Completed: 03/31/2007 5:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

1st. Plug at 2630' w/25 sxs.  
2nd. Plug at 1650' w/100 sxs.  
3rd. Plug at 350' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

RECEIVED  
KANSAS CORPORATION COMMISSION  
APR 26 2007  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

INVOICED  
DATE 5-1-07  
INV. NO. 2007061683

District: 04

Signed Case Morris  
(TECHNICIAN)

APR 18 2007

PKT