

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-153-20499-00-00  
Spot: N2N2NW Sec/Twnshp/Rge: 10-1S-34W  
4960 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: CAHOJ UNIT Well #: 906  
County: RAWLINS Total Vertical Depth: 4352 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	4341	0	w/225 sxs cmt
SURF	8.625	328	0	w/190 sxs cmt

# 141.44

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/18/2007 10:00 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN TURNER Company: MURFIN DRILLING CO., INC. Phone: (785) 462-6781

Proposed Plugging Method: Ordered 350 sxs Midcon II Cement and 1000# hulls.  
Plug through tubing.

Plugging Proposal Received By: HERB DEINES Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/18/2007 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set 328' w/190 sxs cement.  
5 1/2" production casing set at 4341' w/225 sxs cement.  
PBTD 4297'. TD 4352'.  
Production casing had holes.  
Ran tubing to 2500' - pumped 140 sxs cement with 400# hulls.  
Pulled tubing to 1250' - pumped 55 sxs cement with 200# hulls.  
Pulled tubing to 600' - pumped 25 sxs cement - cement to surface.  
Pulled tubing to surface.  
Connected to 5 1/2" production casing - pumped 5 sxs cement.  
Max. P.S.I. 800#. S.I.P. 0#.  
Connected to 8 5/8" surface pipe - pumped 30 sxs cement.  
Max. P.S.I. 150#. S.I.P. 100#.

Perfs:

Top	Bot	Thru	Comments
4056	4284		

Remarks: SWIFT SERVICES, INC.-TICKET #11866.

Plugged through: TBG

**INVOICED**

DATE 5-1-07  
INV. NO. 2007061684

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

RECEIVED  
KANSAS CORPORATION COMMISSION  
Form CP-2/3


APR 27 2007

CONSERVATION DIVISION

APR 19 2007

*DTG*

GETTY OIL COMPANY  
 2705 VINE STREET, UNIT#4 #906 CAHOJ UNIT 10-1-34W  
 HAYS, KS 67601 50' ENL &  
 CONTR MURFIN DRILLING COMPANY CTY RAWLINS 1320' FWL, NW/4  
 GEOL \_\_\_\_\_ FIELD CAHOJ  
 ELV 3138 KB SPD 12/14/83 CARD ISSUED 3/8/84 IP P 26 BO & 110 BWPD  
 3133 GL LKC 4056-4285 OA  
 API 15-153-20,499



LOG	Top	Depth/Datum	
			8 5/8 " 328; 5 1/2 " 4341
			NO DSTS
			MICT - CO, PF (LKC) 4283-4285, 4235-4237, 4082-86, 4060-64,
			4056-66, AC 5400G, SWB LD, T&R, POP, P 26 BOPD & 110
			BWPD, 2/17/84
ANH	2989+	149	
TOP	3852-	714	
OREAD	3934-	796	
DOUG	4000-	862	
LANS	4039-	901	
RTD	4352-	1214	

COPYRIGHT 1983  
 INDEPENDENT OIL & GAS SERVICE, INC.  
 WICHITA, KANSAS