

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01000-00-01
Spot: SENESE Sec/Twnshp/Rge: 31-13S-14W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: BROWN OWWO Well #: 4
County: RUSSELL Total Vertical Depth: 3313 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 15 S. MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3329	0	w/unknown sxs cmt
SURF	8.625	562	0	w/unknown sxs cmt

107.67

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/04/2007 1:30 PM
Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL COMPANY Phone: (785) 483-1543

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/04/2007 4:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Ran tubing to 3300'.
Pumped 50 sxs 60/40 pozmix - 10% gel cement.
Pulled to 2000' - pumped 145 sxs cement.
Pulled to 1000' - circulated with 45 sxs cement.
POOH. Topped off with 10 sxs cement.
Note: Well was squeezed at 900' - 1500' w/100 sxs and 470' w/260 sxs.

Perfs:

INVOICED
DATE 5/11/07
INV. NO. 2007061673

RECEIVED
KANSAS CORPORATION COMMISSION
APR 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY CEMENTING COMPANY.

Plugged through: TBG

District: 04

Handwritten mark

Signed


Case Morris

(TECHNICIAN)

APR 12 2007

Handwritten initials

DRIFTWOOD OIL COMPANY
 BOX 123
 RUSSELL, KS 67665 #4 BROWN "OWWO" 31-13-14W
 SE NE SE
 CONTR RAPID WELL SERVICE CTY RUSSELL
 GEOL _____ FIELD GORHAM
 ELV 1866 OF SPD ^E 3/7/84 CARD ISSUED 8/23/84 IF P 15 BOPD & WTR
ARB 3311.5-3313.5



SMP	Tops	Depth/Datum
4 1/2		918 + 948
HEEB		2979-1113
LANS		3031-1165
ARB		3299-1433
RTD		3300-1434
ODDTD		3313-1447
NDDTD		3330-1464

API 15-167-01,000
 OLD INFO: OPERATOR WAS MURFIN DRILLING CO., #3 BROWN, SPD 11/15/50, SET 8 5/8 " 562, 5 1/2 " 3300, COMP. AS P 25 BOPD, ARB OH 3300-3313, (CARD ISSUED 12/29/50), CONTR: UNKNOWN
 MICT - CO TO RTD (ARB OH), DD 3306 TD, NS, DD 3310 TD, FU 800' OIL / 12 HRS, NAT, DD 3313 TD, AC 500 G, FU 1100' OIL / 11 HRS, POP
 NEW INFO: FR 2/10/84, RE-ENTERED E 3/7/84, WSH DWN TO ODDTD, SO IN TARK & TOP, NEW DD 3330 TD, SET 4 1/2 " LINER 3329, MICT - CO, PF (ARB) 3311.5-13.5, AC 400G (7.5%), SWB DWN. SO. POP. P 15 BOPD & WTR, 8/1/84

COPYRIGHT 1984
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS