

TO: STATE CORPORATION COMMISSION

API Well Number: 15-051-22443-00-00

Spot: SWNWSE Sec/Twnshp/Rge: 12-14S-19W

1650 feet from S Section Line, 2310 feet from E Section Line

Lease Name: BEFORT

Well #: 1

County: ELLIS

Total Vertical Depth: 3835 feet

Notes/Comments
10/28/06 - Invoices should be sent to:
CWB Co., PO Box 186, Hays, KS 67601 (pim)

Operator License No.: 32875

Op Name: CWB - CO, A GENERAL PARTNERSHIP

Address: 40837 BEAR CREEK ROAD
SPRINGVILLE, CA 93265

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3838	0	w/unknown sxs cmt
SURF	8.625	208	0	w/unknown sxs cmt

\$124.04

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 04/18/2007 9:00 AM

Plug Co. License No.: 32332

Plug Co. Name: FISCHER PIPE TESTING, INC. DBA FISCHER WELL SERVICE

Proposal Rcvd. from: JAMES HERTEL

Company: CWB-CO, A GENERAL PARTNERS

Phone: (785) 628-2593

Proposed Plugging Method: Ordered out 275 sxs 60/40 pozmix - 10% gel - 500# hulls.
Note: Please send invoice to: SWB Co., P.O. Box 186, Hays, Kansas 67601

Plugging Proposal Received By: JAY PFEIFER

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 04/18/2007 1:30 PM

KCC Agent: JAY PFEIFER

Actual Plugging Report:

Perforated casing at 700' - 1450' - 2100'.
TIH with tubing to 2500' - mixed and pumped 75 sxs cement with 500# hulls.
Pulled up to 1000' - circulated cement with 125 sxs.
POOH. Topped with 25 sxs.
Hooked up to the annulus and pumped 25 sxs.
S.I.P. 400#.

Perfs: INVOICED

DATE 5-1-07

INV. NO. 2007061674

RECEIVED

APR 23 2007

KCC WICHITA

RECEIVED

23 2007

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed

Jay Pfeifer

(TECHNICIAN)

APR 19 2007

PP

STAAB-DREILING OIL CO
 2507 FORT ST #1 BEFORT
 HAYS, KS PIONEER DRILLING CO CTY ELLIS
 CONTR _____

12-14-19W
 SW NW SE

GEOL LEWIS CHUBB FIELD RIDGE HILL

E 2181 KB CM 6/21/81 ^{CARD} ISSUED 9/3/81 IP P 16 BOPD, TR WTR
 ARB 3785-3790

+	+	+
+	+	+
+	+	+

API 15-051-22,443

LOG	TOPS	DEPTH	DATUM
ANH		1437	+ 744
B ANH		1482	+ 699
TOP		3176	- 995
HEEB		3438	- 1257
TQR		3458	- 1277
LANS		3486	- 1305
BKC		3714	- 1533
CONG		3750	- 1569
ARB		3784	- 1603
RTD		3835	- 1654
LTD		3839	- 1658

8 5/8" 208; 4 1/2" 3838
 DST (1) 3782-95 (ARB) / 0-30-0-45
 120' GIP, REC 120' MDY OIL, 360'
 CL OIL (TOOL PLUGGED ON INITIAL
 OPEN), SIP 683-653#, NO IFP/
 144-180#, BHT 122°
 MICT - CO, PF (ARB) 3785-90, AC250G
 (MA), SWB 2 1/2" BOPH THRU 2" TBG, POP
 (LKC PAY REMAINS BEHIND PIPE)

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS