

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-24420-00-00
Spot: SESWNENW Sec/Twnshp/Rge: 2-22S-18E
1145 feet from N Section Line, 3540 feet from E Section Line
Lease Name: J. WALTER Well #: 1
County: ANDERSON Total Vertical Depth: 1200 feet

Operator License No.: 8509
Op Name: EVANS ENERGY DEVELOPMENT, INC.
Address: 11 LEWIS DR.
PAOLA, KS 66071

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20	0	

\$ 39.00

Well Type: Oil DH ^{KCC PER} UIC Docket No: _____ Date/Time to Plug: 04/10/2007 4:30 PM
Plug Co. License No.: 8509 Plug Co. Name: EVANS ENERGY DEVELOPMENT, INC.
Proposal Rcvd. from: SCOTT EVANS Company: EVANS ENERGY DEVELOPMENT, INC. Phone: (913) 259-1202

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASSED 5 5/8" BORE TO 1230'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 500', AND CONTINUOUS CEMENT PLUG FROM 250' TO SURFACE.

Plugging Proposal Received By: RON ROWE Witness Type: NONE
Date/Time Plugging Completed: 04/10/2007 4:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report: _____ Perfs: _____

1" PIPE WAS RAN INTO THE WELL TO 1200'. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 1" PIPE TO 1200'. THE PIPE WAS PULLED TO 500' AND 10 SACKS OF CEMENT WERE PUMPED THROUGH THE PIPE TO THAT DEPTH. THE 1" PIPE WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED
KCC DISTRICT #3
APR 18 2007 CPT
CHANUTE, KS

RECEIVED
KANSAS CORPORATION COMMISSION
APR 26 2007
CONSERVATION DIVISION
WICHITA, KS

INVOICED
DATE 5-1-07
INV. NO. 2007061676

Remarks:
Plugged through: TBG

District: 03 Signed Clayton P. Titel
(TECHNICIAN)

AKS