

X

"AMENDED"

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-20228-00-00
Spot: CE2E2SW Sec/Twnshp/Rge: 28-20S-13W
1324 feet from S Section Line, 2970 feet from E Section Line
Lease/Unit Name: PURSEL UNIT Well Number: 7
County: BARTON Total Vertical Depth: 3505 feet

Operator License No.: 32000
Operator Name: ALB, INC.
Address: PO BOX 173
GREAT BEND, KS 67530

Conductor Pipe: Size _____ feet:
Surface Casing: Size 8.62 feet: 335
Production: Size 5.5 feet: 3500
Liner: Size _____ feet:

\$ 113.91

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 9/27/00 9:30:00 AM
Plug Co. License No.: 32000 Plug Co. Name: ALB, INC.
Proposal Rcvd. from: CRAIG BIGGS/DANNY BIG Company: ALB, INC. Phone: (316) 793-8366

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 10% gel - 20 sxs gel spacer - 300# hulls.
Prod Perfs 3340' - 3344'; 3401' - 3407'; 3432' - 3442'.

Plugging Proposal Received By: HUBERT DEINES WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 09/27/2000 10:45 AM KCC Agent: JAY PFEIFER

Actual Plugging Report:

8 5/8" set at 335' w/300 sxs. 5 1/2" set at 3500' w/65 sxs.
Tied onto 5 1/2" and pumped 50 sxs cement w/300# hulls, followed by 20 sxs gel spacer and topped with 85 sxs cement.
Max. P.S.I. 1000#. S.I.P. 600#.
Tied onto casing annulus and pumped 65 sxs. S.I.P. 100#.

INVOICED
DATE 10-13-00
INV. NO. 2001060818

Remarks:

Plugged through: CSG

District: 04

Signed

(TECHNICIAN)


RECEIVED Form CP-2/3
KANSAS CORPORATION COMMISSION

MAY 01 2007

CONSERVATION DIVISION
WICHITA, KS

OCT 05 2000

PHILLIPS PETROLEUM CO. #7 PURSEL UNIT 28-20-13W
 GREAT BEND, KS C E2 E2 SW
 Contr. LEBEN DRLG Cty. BARTON
 Geol. CO. GEOL Pool SANDROCK
 E. 1885 GR Cm. 5/18/68 Cp. 6/27/68 IP P 49 BOPD + 110
 API 15-009-20,228 BW/LKC 3340-44,
 3401-07, 3432-42



Tops	Depth	Datum
Awh	737	+1148
RTD	3501	

Csg. 8" 320/300 sx, 5" 3500

NO TESTS
 NO CORES
 NO TOPS
 NO LOG

PF 3432-42, A 1250, /3401-07
 A 750, /3340-44, A 500.

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS