

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01026-00-01
Spot: NENESW Sec/Twnshp/Rge: 32-13S-14W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BOXBERGER Well #: 1
County: RUSSELL Total Vertical Depth: 3296 feet

Operator License No.: 32322
Op Name: DENIS F. ROBERTS
Address: BOX 1252 3904 FAIRWAY DR.
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3298	0	w/75 sxs cmt \$ 107.12
SURF	8.625	178	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/09/2007 9:00 AM
Plug Co. License No.: 32030 Plug Co. Name: DOC'S WELL SERVICE, INC.
Proposal Rcvd. from: DOC Company: DENIS F. ROBERTS Phone: (785) 625-8526

Proposed
Plugging
Method:

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/09/2007 1:00 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

Perfs:

Packer in bottom of hole.
Ran tubing to 3240'.
Pumped 125 sxs 60/40 pozmix - 10% gel cement with 400# hulls.
Pulled to 1600'. Circulated with 100 sxs cement with 200# hulls.
POOH. Tied onto casing and pumped 75 sxs cement.
Max. P.S.I. 100#. S.I. P. 100#.

INVOICED
DATE 5-1-07
INV. NO. 2007061688

RECEIVED
KANSAS CORPORATION COMMISSION
APR 26 2007
CONSERVATION DIVISION
WICHITA, KS

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed _____

(TECHNICIAN)

APR 12 2007

replacement card

ATHOL BARTON OIL
RUSSELL KS 67665


32-13 -14W
NE NE SW

#1 BOXBERGER OWWO

site: 1-1/2 W OF RUSSELL KS
contr: SUPER OILWELL SVC

city: RUSSELL
field: GORHAM

API 15-167-01026-00-01



fr date 04/05/90 spd date 10/13/90 drig comp 10/13/90 card issued 01/07/91 last revised 02/10/92

ELV: 1862 KB, 1857 GL SMP
tops.....depth/datum
HEEB.....2972 -1110
LANS.....3027 -1165
ARB.....3292 -1430
RTD OLD.....3296 -1434
DDTD.....3298 -1436

Arch
893 + 969
FL 800-960
Arch - Depth

IP status:
OIL, P 10 BO & 300 BWP, ARB 3293-3298 ,
CORR & INFO REL: 2/10/92 - CORRECTED ELEV & CSG;
ADDED MISC INFO
OLD INFO: OPERATOR WAS EL DORADO REFINING /
AYLWARD DRILLING, 1 BOXBERGER, SPD 02/01/49 , 8-
5/8" 178 (ALT 2), 5-1/2" 3292, OIL, P 100 BOPD, ARB
3293-3296 , (CARD ISSUED 03/18/49)
CONTR: AYLWARD DRILLING
NO CORES OR DSTS
MICT - CO, (ARB OH), SWB 8.5 BOPH/8 HRS, NAT, POP,
P EST 100 BOPD, NW
NEW INFO: FR 04/05/90 , RE-ENTERED 10/13/90 WSH
DWN, SQZ'D DC 10/13/90 CSG: PROD CSG ALREADY IN
HOLE TRGT ZN: ARB, PTD 3298 (ARB), MICT - CO, (ARB
OH), DD 3298 TD, SO, SET 2-1/2" TBG AT 3275, NO PKR,
POP, P 10 BO & 300 BWP 11/28/90

COPYRIGHT 1992
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS

12