

STATE OF KANSAS
STATE CORPORATION COMMISSION
100 COLORADO DERRY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

API NUMBER _____

LEASE NAME Reener Estate

WELL NUMBER _____

SPOT LOCATION C SE NW

SEC. 28 TWP. 9s R(±) 20w(E) 0

LEASE OPERATOR Rains & Williamson Oil Co., Inc.

ADDRESS 435 Page Court Bldg. 220 W. Douglas, Wichita, Ks. 67202 COUNTY Rooks

PHONE #() _____ OPERATORS LICENSE NO. _____

DATE WELL COMPLETED _____

PLUGGING COMMENCED 1/5/84

CHARACTER OF WELL
(OIL, GAS, I&A, SWD, INPUT, WATER SUPPLY WELL)

PLUGGING COMPLETED 1/11/84

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Hays

IS ALC-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3860'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	246'	none
				5 1/2"	3854'	2508'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

Put 5 sacks cement, sand & 5 sacks cement to 3800'. Shot casing at 3014', 2811', and 2508'. Pulled total of 63 joints. Plugged well with 3 hulls, 15 gel with hull, 100 cement with hulls, 12 gel with hull, released plug & 70 sacks 50/50 poz. 6% gel 3% c.c. Plugging complete.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Kelso Casing Pulling LICENSE NO. 6050
ADDRESS Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, SS.

R. Darrell Kelso (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

RECEIVED
STATE CORPORATION COMMISSION
1-18-84
JAN 18 1984
CONSERVATION DIVISION
Wichita, Kansas

(SIGNATURE) R. Darrell Kelso
(ADDRESS) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO BEFORE ME THIS 12th DAY OF January, 1984

Irene Hoover
NOTARY PUBLIC



MY COMMISSION EXPIRES: _____

COPY