

Give  
Make  
Mail or E  
Conservation Division  
State Corporation Commission  
211 N. Broadway  
Wichita, Kansas

10

15-163-19102-00-00

WELL PLUGGING RECORD

Rocks \_\_\_\_\_ County, Sec. 33 Twp. 9 Rge. \_\_\_\_\_ (E) 20 (W)

Location as "NE/CNW/SE/SW" or footage from lines S/2 SW SW

Lease Owner Quality Supply Co.

Lease Name Marcotte Well No. 1

Office Address 701 Union National Bldg. Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_

Date well completed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_

Application for plugging approved \_\_\_\_\_ 19 \_\_\_\_\_


Plugging commenced \_\_\_\_\_ 8-22 19 61

Plugging completed \_\_\_\_\_ 8-22 19 61

Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty 3844 KCC

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3827 TA Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
						no casing pulled

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Well had been squeezed @ top-no recovery possible-  
Called pump truck-pumped in 40 sks of Gel mud and  
85 sks cement

RECEIVED  
STATE CORPORATION COMMISSION  
9/29/61  
CONSERVATION DIVISION  
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor R and D Casing Pulling Co.

Address Box 572, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgewick, ss.

Jack Shear (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Quality Supply Company Jack Shear  
701 Union National Bldg  
(Address)

SUBSCRIBED AND SWORN TO before me this 26<sup>th</sup> day of Sept. 26, 1961

Evelyn V. North  
Notary Public.

My commission expires Dec. 22, 1962



19-163-19102-20-d

Date Spudded: July 29, 1944  
Dflg. Completed: August 29, 1944  
Temporary Potential: August 29, 1944

Loc: 350'W and 350'E of S.W.  
corner of Sec. 33, T9S, R30W,  
Rooks County, Kansas

FROM	TO	FORMATION	FROM	TO	FORMATION
0	120	Surface soil & sand	1805	1866	Red bed & shells
120	400	Sand & shale	1866	2170	Shale & shells
400	850	Shale & shells	2170	2635	Lime & shale
850	1260	Sand, shells & shale	2635	2895	Broken lime & shale
1260	1455	Sand	2895	3050	Lime
1455	1650	Sand & shale	3050	3340	Broken lime & shale
1650	1740	Red bed & shale	3340	3844	Lime
1740	1805	Anhydrite			

Elevation 2257'

Top of Arbuckle Lime 3844'

Ran 240' of 10 3/4"OD 29# 50cuage Armeo Spiral Weld casing; set at 239'; cemented with 340 sacks of Portland Lone Star cement (Halliburton method).

Ran 3659'2" of 6"OD 18# SRT Grade "H-40" Electric Weld casing; ran 6"OD SRT "Halcolite" male and female float collar and guide shoe; set at 3939'; cemented with 300 sacks of Portland Red Ring cement (Halliburton method).

8/28/44 - Drilled out plug - hole filled 2600' with oil in 6 hours.

8/29/44 - Swabbed 212 bbls, oil in 2 1/2 hours at 2000' off bottom.

8/29/44 - Established 25 dbl, minimum temporary swabbing potential.

Total Depth 3844' in Arbuckle Lime.

Note: Footages are from pumping derrick floor level, except formations.

I, the undersigned, being first duly sworn upon oath, state that this Well Record is true, correct and complete, according to the records of this office, and to the best of my knowledge and belief.

Assistant District Superintendent

Subscribed and sworn to before me this 27th day of November, 1944.

Notary Public

My commission expires October 21st, 1948.

WmD-MFD  
11-27-44  
LPC 3

File

RECEIVED  
STATE CORPORATION COMMISSION

AUG 4 1961

CONSERVATION DIVISION  
Wichita, Kansas