

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

WELL PLUGGING RECORD

Rooks County. Sec. 33 Twp. Rge. 9.5 (E) 20 (W)

Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines 7N-SW-SW-339S-20W.

Lease Owner Lohman, John Dily Co.

Lease Name Marsathe #14 Well No. L.H.

Office Address 320 2nd Bank Bldg. Lamont Indian

Character of Well (completed as Oil, Gas or Dry Hole) oil.

Date well completed 11-25 1947

Application for plugging filed 4-8 1953

Application for plugging approved 4-10 1953

Plugging commenced 4-16 1953

Plugging completed 4-21 1953

Reason for abandonment of well or producing formation Drift sand

Plugging hole.

If a producing well is abandoned, date of last production 3-6 1953

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Arbuckle Depth to top Bottom Total Depth of Well Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	350'	None
				5 1/2"	3837'	1215'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

tubing was cut off @ 3595', dumped 4 sag of cement @ 3595' with hand bailer. Top of cement 3565'. filled hole with rotary bit mud to 350'. This mud was shoveled into hole, set 10' rock bridge @ 350'. dumped 15 sag of cement, top of cement 308'. filled hole with mud to 30'. set 10' rock bridge, dumped 10 sag of cement for cap.

Name of Plugging Contractor Miller Casing Pulling Co. (If additional description is necessary use BACK of this sheet)  
Address Box 711 Great Bend Kansas

STATE OF Indiana COUNTY OF Vanderburgh, ss.  
W. L. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. L. Johnson

SUBSCRIBED AND SWORN to before me this 28th day of April, 1953

My commission expires Nov 5, 1953 Walter Fields Notary Public.

**PLUGGING**  
FILE SEC 33 T 9 R 20W  
BOOK PAGE 93 LINE 18

23-8390-s 6-51-20M  
RECEIVED  
CORPORATION COMMISSION  
4/30/53  
APR 30 1953  
CONSERVATION DIVISION  
Wichita, Kansas

15-163-03513-00-00


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- LOHMANN & JOHNSON  
Farm- Marcotte "A" No. 1

SEC. 33 T. 9 R. 20W  
NW SW SW

Total Depth. 3845  
Comm. 11-5-47 Comp. 12-3-47  
Shot or Treated.  
Contractor.  
Issued. 1-12-52

County Rooks  
KANSAS



CASING:  
8" 3541  
5" 3837

Elevation. 2267

Production. 490 BO

Figures Indicate Bottom of Formations.

NO LOG AVAILABLE

**PLUGGING**  
SEC. 33 T. 9 R. 20W  
PAGE 93 LINE 18

RECEIVED  
STATE COMMISSION  
JUN 13 1953  
CONSERVATION DIVISION  
WICHITA, KANSAS

LOHMANN - JOHNSON

Drilling Company, Inc.



OFFICES IN

EVANSVILLE, IND. • 320 INDIANA BANK BLDG. • TEL. 4-1032  
DENVER, COLO. • 352 COLORADO NAT'L BANK BLDG. • TEL. KEYSTONE 1582  
WICHITA, KANSAS • 533 PETROLEUM BLDG. • TEL. 5-7787  
CALGARY, ALBERTA, CANADA

REPLY TO:  
EVANSVILLE, INDIANA

June 11, 1953

S. S. Greider  
T. A Morgan, Director  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

Re: Marcotte Well No. 1-A  
NW SW SW Sec. 33-9-20W  
Rooks County , Kansas

Dear Mr. Greider:

In reply to your letter of May 28 pertaining to Well Log on above caption in connection with plugging application or record received by you under date of April 30 from this office.

We made up a Well Record on this well and forwarded to your office in 1946 when the well was drilled but since then we have discarded our records on this and are unable to furnish you with an additional Well Log as we do not have the original Daily Drilling Reports.

Very truly yours,

LOHMANN-JOHNSON DRILLING CO., INC.

W. L. Johnson  
wlj/hf

