

WELL PLUGGING RECORD

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

OR
FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging off formations.

**Strike out upper line
when reporting plug-
ging off formations.**

NORTH

[illegible]

**Locate well correctly on above
Section Plat**

Rooks County, Sec. 33 Twp. 9 Rge. 20 (E) W (W)
Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner C-G Drilling Co. Inc.
Lease Name Fesler Well No. I
Office Address 206 Union Natl Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) dry hole
Date well completed September 7, 1949
Application for plugging filed September 7, 1949
Application for plugging approved September 7, 1949
Plugging commenced September 7, 1949
Plugging completed September 7, 1949
Reason for abandonment of well or producing formation Too low structurally.

If a producing well is abandoned, date of last production.....19.....
Was permission obtained from the Conservation Division or its agents before plugging was commenced?.....**Yes**.....

Name of Conservation Agent who supervised plugging of this well..... Eldon Petty, Great Bend, Kansas.....
Producing formation..... Depth to top..... Bottom..... Total Depth of Well..... Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

[illegible]

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet tofeet for each plug set.

Filled with drilling mud to 251'. Drove plug to 250'. Put in 15 sacks cement then pumped full of mud 25' from top of hole. Drove plug down to 25' then filled to top with 10 sacks of cement.

RECEIVED

9/10/49

SEP 10 1949

STATE CORPORATION
COMMISSION
KANSAS

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to C-G Drilling Company
Address 206 Union Natl Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

R. A. Cook (~~employee of owner~~) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-
described well as filed and that the same are true and correct. So help me God. *R A C*

(Signature)

206 Union Natl Bank Bldg.

(Address)

SUBSCRIBED AND SWORN to before me this 9th day of September, 1949

My commission expires..... June 25, 1951

22-2625

2-48—15M

Notary Public.

FILE NO. 33-9-3004
BOOK PAGE 113 LINE 21

CONTRACTOR'S WELL LOG

Operator C-G Drilling Co. Inc. Farm Name Fesler No. I
 Location NE $\frac{1}{4}$ NE $\frac{1}{4}$ NE $\frac{1}{4}$ Sec. 33-9-20W.
 Pool Name WC County Rooks State Kansas
 Commencement Date 8-26-49 Completion Date 9-7-49

LOG OF WELL

Elevation 2267' DF

All measurements from the top of rotary bushing.

DEPTH		FORMATION	DEVIATION FROM VERTICAL	REMARKS:
FROM	TO			
0	250	Shale-Shells		
250	670	Shale		
670	920	Shale-Shells		
920	1500	Shale-Sand-Shells		
1500	1763	Shale-Shells		
1763	1795	Anhydrite		
1795	1860	Shale-shells		
1860	2190	Shale-Shells	2000' - 0°	
2190	2320	Shale-Lime		
2320	2470	Shale-Lime		
2470	2550	Lime-Shale	2500' - 0°	
2550	2700	Lime-Shale		
2700	2770	Lime-Shale	2750' - 0°	
2770	2855	Lime		
2855	2900	Lime		
2900	3015	Lime-Shale	3000' - 0°	
3015	3080	Lime-Shale		
3080	3150	Lime-Shale		
3150	3225	Lime-Shale		
3225	3295	Lime-Shale	3250' - 0°	
3295	3390	Lime-Shale		
3390	3490	Lime-Shale		
3490	3540	Lime-Shale		
3540	3585	Lime		
3585	3635	Lime		
3635	3685	Lime		
3685	3730	Lime		
3730	3785	Lime		
3785	3830	Lime		
3830	3863	Lime		
3863	3873	Lime		

CASING LEFT IN HOLE AFTER COMPLETION

250.45' (8 jts.) 8-5/8" OD Casing.

STATE OF KANSAS, COUNTY OF SEDGWICK) SS.

The undersigned certifies that to the best of his knowledge and belief
 the above facts are true and correct.

C-G DRILLING COMPANY, Inc.

By R. A. Cook, President

Subscribed and sworn to before me this 9th day of September, 1949.

My commission expires:
 June 25, 1951

Vicki Lutz
 Notary Public

