


15-163-03515-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Rooks County. Sec. 33 Twp. 9S Rge. 20 ~~XXX~~ (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SE SW SE
Lease Owner Lohmann-Johnson Drilling Co., Inc.
Lease Name Marcotte "B" Well No. 3
Office Address 320 Indiana Bank Bldg., Evansville, Indiana
Character of Well (completed as Oil, Gas or Dry Hole) Oil Well
Date well completed 9/10/50 19.....
Application for plugging filed 19.....
Application for plugging approved 19.....
Plugging commenced 5/28/52 19.....
Plugging completed 5/29/52 19.....
Reason for abandonment of well or producing formation No longer producing
a commercial quantity of oil.
If a producing well is abandoned, date of last production April 10, 19 52
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above
Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Arbuckle Depth to top 38.49 Bottom 38.50 Total Depth of Well 3852 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8	364	
				5 1/2		2883

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from.....feet to.....feet for each plug set.

Plugged back with crushed rock to 3845, dumped 4 sacks cement with dump bailer, top of cement 3815'. Mudded hole to 360', set rock bridge, dumped 15 sacks cement, top of cement 315'. Mudded hole to 35', set rock bridge, dumped 10 sacks for cap.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lohmann-Johnson Drilling Co., Inc.
Address 320 Indiana Bank Building, Evansville, Indiana

STATE OF Indiana, COUNTY OF Vanderburgh, ss.
James W. Kendall (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Kendall
320 Indiana Bank Building, Evansville, Ind.
(Address)

SUBSCRIBED AND SWORN to before me this 12th day of June, 19 52

Notary Public. (Signature)

My commission expires October 14, 1953.

PLUGGING
FILE REC 33T 9 R 20
BOOK PAGE 20 LINE 3

RECEIVED
6/14/52
JUN 14 1952
CONSERVATION DIVISION
Wichita, Kansas

15-163-03515-00-00

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- LOHMANN & JOHNSON
Farm- Marquette "B" No. 3

SEC. 33 T. 9 R.20W
SE SW SE

Total Depth. 3852
Comm. 7-5-50 Comp. 9-13-50
Shot or Treated.
Contractor.
Issued. 1-12-52

County Rocks
KANSAS



CASING:

Elevation. 2265

Production. 100 BO @ 82% wtr.

Figures Indicate Bottom of Formations.

NO LOG AVAILABLE

Scout Tops:	
Hobner	3502
Dolomite	3524
Lansing	3542
Simpson Dolo.	3833
Gr. Shale	3842
Arbuckle	3850

PLUGGING
 FILE SEC 33 T 9 R 20W
 BOOK PAGE 20 LINE 3

RECEIVED
 STATE OF KANSAS
 COMMISSIONER OF GEOLOGY
 WICHITA, KANSAS