


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Make or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Rooks County. Sec. 33 Twp. 9S Rge. 20W ~~XXXXXX(W)~~

Location as "NE/CNW¹/₄SW¹/₄" or footage from lines SW SW NE
Lease Owner Marcotte Lohmann-Johnson Drilling Co., Inc.
Lease Name Marcotte Well No. A-2
Office Address 320 Indiana Bank Building, Evansville, Indiana
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed February 20 19 48
Application for plugging filed April 25 19 54
Application for plugging approved April 25 19 54
Plugging commenced April 25 19 54
Plugging completed April 25 19 54
Reason for abandonment of well or producing formation non-producing
If a producing well is abandoned, date of last production April 6 19 54
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3851 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged back with crushed rock from 3857 ft. to 3840 ft.
Dumped 4 sacks cement at 3480' with dump bailer, top of cement 3812' - Filled hole with mud through casing to 350 ft.
Set rock bridge at 350 ft. - Dumped 15 sacks cement. Top of Cement 295 ft.
Filled with Mud to 35 ft. -
Set Rock bridge - dumped 10 sacks cement for cap

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Lohmann-Johnson Drilling Co., Inc.
Address 320 Indiana Bank Building, Evansville, Indiana

STATE OF Indiana, COUNTY OF Vanderburgh, ss.
W. L. Johnson (employee or owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) By M. R. Johnson, Lohmann-Johnson Drilling Co., Inc.
320 Indiana Bank Building, Evansville, Indiana (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of May, 19 54

My commission expires November 5, 1957

RECEIVED
5/20/54
Notary Public.

PLUGGING
FILE SEC 33 T 9 R 20W
BOOK PAGE 27 LINE 33

C
O
P
Y

WELL LOG

CLARENCE WOOD ETAL

Marcotte #2-A

Described as Marcotte Well No. 2
located in Rooks County, Kansas

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>
Surface	0	131
Shale & Shells	131	379
Shale & Shells	379	987
Shale, shells, sand	987	1416
Shale & Shells	1416	1769
Anhydrite	1769	1800
Shale & Shells	1800	1921
Shale & Shells	1921	2096
Shale & Shells	2096	2447
Lime & Shale	2447	2467
Shale & Shells	2467	2527
Shale & Shells	2527	2610
Lime & Shale	2610	2955
Lime	2955	3005
Lime & Shale	3005	3482
Lime	3482	3820
Lime & Shale	3820	3847
lime Arbuckle	3847	3851
TOTAL DEPTH	3851	

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1954
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 22 T 9 R 20W
BOOK PAGE 27 LINE 33