

15-163-02455-00-00

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Rooks County, Sec. 36 Twp. 9S Rge. (E) 20 (W)

Location as "NE/CNW/SW" or footage from lines ~~NW SE NE/4~~ NW SE NW KCC CAP

Lease Owner Herman Geo. Kaiser, Oil Producer

Lease Name Gish "B" Well No. 5

Office Address 908 Palace Building, Tulsa 3, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 13, 19 55

Application for plugging filed " " 19 "

Application for plugging approved " " 19 "


Plugging commenced " " 19 "

Plugging completed " " 19 "

Reason for abandonment of well or producing formation dry

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3830 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	208'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 203 ft., set plug at 203 ft.  
and cemented with 20 sacks cement and 1/3 sack hulls. Mud to  
40 ft., set plug and cemented with 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.  
Address 710 Petroleum Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss. L. C. Sponenberg employee of Contractor  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) L. C. Sponenberg  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN TO before me this 18th day of April, 19 55

My commission expires February 13, 1956.

Rose Fusley  
Notary Public.

PLUGGING  
FILE SEC 36 T 9 R 20W  
BOOK PAGE 111 LINE 28

4/21/55  
CONSERVATION DIVISION  
WICHITA, KANSAS

15-163-02455-00-00

**KANSAS GEOLOGICAL SOCIETY**  
**KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU**  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COMPANY **Herman Geo. Kaiser, Oil Producer**

SEC. **36** T. **9** R. **20**

FARM **Gish B** NO. **5**

LOC. **NW 38 XV**

TOTAL DEPTH **3830'**

**4/13/55 KCC**  
**2AP**

COUNTY **Toots**

COMM. **3/31/55**

COMP. **4/25/55**

KANSAS

SHOT OR TREATED

CONTRACTOR **H-30, Inc.**

ISSUED


CASING

20	10
15	8 <b>208'</b>
12	6
13	5

ELEVATION **2232 D.F.**  
**2235 K.B.**  
PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

Shale, Clay & Sand	208
Shale	910
Shale & Sand	960
Shale	1190
Sand	1400
Shale, Shells & Red Bed	1665
Iron Pyrite, Shale & Red Bed	1705
Anhydrite	1740
Iron, Shale & Red Bed	1797
Shale, Shells & Iron	2190
Shale, Red Bed & Lime	2302
Shale & Lime	3192
Lime	3527
Shale, Lime & Chert	3559
Shale & Lime	3599
Lime	3675
Lime & Shale	3714
Lime & Chert	3759
Lime & Chert	3777
Chert	3792
Lime & Chert	3823
Shale & Lime	3830

FORMATION TOPS

NECENET	3452
TORONTO	3478
LANSING	3491
BASE KANSAS CITY	3708
CONGLOMERATE	3790
SIMPSON	3798
ARBuckle	3816

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

By *C.P. Sprouling*

STATE OF KANSAS |  
                          | ss:  
COUNTY OF SEDGWICK |

Subscribed and sworn to before me, a notary public, in and for said County and State this 18th day of April, 1955.

**PLUGGING**  
FILE SEC. 36 T. 9 R. 20W  
BOOK PAGE 11 LINE 28

*Rose Turey*  
Notary Public

My Commission expires February 19, 1956.