

15-163-01028-00-0

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER None

LEASE NAME Gish B.

WELL NUMBER 1

330 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 36 TWP. 9S RGE. 20 (●) or (W)

COUNTY Rooks

Date Well Completed 12/14/52

Plugging Commenced 2/9/88

Plugging Completed 2/9/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-25-88 (date)

by District #4, Hays (KCC District Agent's Name).

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation Arbuckle Depth to Top 3774 Bottom 3782 T.D. 3782

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Arbuckle	Oil	3774	82	8-5/8	197	-0-
				5-1/2	3778	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pumped 150 sxs thrifty-mix + 5 sxs hulls from TD to surface. Pumped 50 sxs thrifty-mix down annulus.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) C. Jan Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121-1468

SUBSCRIBED AND SWORN TO before me this 17th day of February, 19 88

Deborah L. Harrell
Notary Public

My Commission Expires: 12-6-89

LOG

Company: Francis Oil & Gas, Inc.
 Contractor: Woody Speer
 Drilling Commenced: 11/29/52
 Drilling Completed: 12/14/52
 Elevation:

Farm: Gish B #1
 Location: C S/2 SW SW/4 Sec. 36-98-20W
 Rooks County, Kansas
 Casing Record: 8-5/8" casing at 197'
 with 150 sacks cement.
 5 1/2" casing at 3778' with 125
 sacks cement.

(figures below indicate bottoms)

Shale & Sand	193
Shale & Shells	800
Shale	920
Sand	960
Shale	1080
Sand & Shale	1120
Sand	1100
Shale & Shells	1170
Red Bed	1550
Shale & Shells	1686
Anhydrite	1720
Shale	1725
Shale & Lime	2230
Lime	2580
Lime & Shale	3305
Lime	3461
Lime & Shale	3512
Lime	3615
Lime & Shale	3643
Lime	3710
Lime & Shale	3759
Conglomerate	3782
R.T.D.	3782

I hereby certify that this is a true and correct log of the above described well as shown by the drilling reports.

WOODY SPEAR

By *W. L. Speer*

STATE OF KANSAS

COUNTY OF SEDGWICK

ss:

Subscribed and sworn to before me, a notary public, in and for said County and State this 19th day of December, 1952.

Lorraine M. Johnson
 Notary Public

My Commission Expires: Oct 13, 1956
~~Sept. 17, 1955.~~

21 1986

NOTARY PUBLIC