


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Rooks County. Sec. 36 Twp. 9 Rge. 20 (E) (W)
Location as "NE/CNW/SW" or footage from lines E/2 SE SE
Lease Owner White & Ellis Drilling, Inc.
Lease Name Pywell Well No. 1
Office Address P. O. Box 1418 El Dorado, Kansas 67042
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 3-20-70 _____ 19____
Plugging completed 3-30-70 _____ 19____
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3786 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	235	None
				5 1/2	None	999'.55

RECEIVED
STATE CORPORATION COMMISSION
4/9/70
APR 9 1970
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Dug cellar. Moved unit into location. Got stuck and had to hire truck to set in rig. Rigged up pole.

Sanded back to 3600' and dumped 5 sacks of cement. Rigged up jacks, had 9" tension. Shot casing at 3004'. Spotted oil at 3004'.

Working casing and shot casing at 1500' and 1004'. Pulled 10 joints of range #3 5 1/2" casing.

Finished pulling 14 joints of 5 1/2" casing. Loaded trailer, tore down rig and moved off location.

Allied Cementing squeezed well with 28 sacks of mud, 5 sacks of hulls and 120 sacks of pozmix cement.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Forbes Casing Pulling Company, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas, COUNTY OF Barton, ss.
James W. Rockhold (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James W. Rockhold
P. O. Box 221 Great Bend, Kansas
(Address)

Subscribed AND SWORN TO before me this 7 day of April, 19 70



Notary Public.

15-163-01797-00-00

CASING RECORD

8 5/8" 235' Cemented
w/200 sacks

5 1/2" 3775' Cemented
w/125 sacks

Total Depth 3786'

Location: C-E/2 SE-SE
Section: 36-9S-20W
Rooks County, Kansas
Farm: Pywell #1
Well Owner: WHITE & ELLIS
DRILLING, INC.
Contractor: Stickle Drilling Co.
Commenced: 12-16-50
Completed: 12-31-50

<u>FORMATION</u>	<u>DEPTH</u>
Surface Clay	0-20
Sand	20-40
Shale	40-237
Shale & Shells	237-740
Sand	740-765
Shale & Shells	765-1070
Sand	1070-1125
Shale & Shells	1125-1650
Anhydrite	1650-1700
Shale & Shells	1700-2000
Shale	2000-2170
Shale & Shells	2170-2275
Lime & Shale	2275-2385
Lime	2385-2775
Lime & Shale	2775-2850
Lime	2850-3005
Shale & Shells	3005-3110
Lime	3110-3150
Shale & Lime	3150-3265
Lime & Shale	3265-3345
Lime	3345-3777 RTD

Drilled with cabletool to 3786'.

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1970
CONSERVATION DIVISION
Wichita, Kansas