


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Biting Building
Wichita, Kansas

Rooks County, Sec. 36 Twp. 9 S. Rge. 20 (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$
Lease Owner Barnett Drilling, Inc., et al
Lease Name Steeples Well No. 1
Office Address 623 First National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed July 28, 19 51
Application for plugging filed July 28, 19 51
Application for plugging approved July 28, 19 51
Plugging commenced July 28, 19 51
Plugging completed July 28, 19 51
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty
Producing formation Depth to top Bottom Total Depth of Well Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|----------------|---------|------|---------|--------|---------|------------|
| Surface Casing | | 0 | 150 Ft. | 8 5/8" | 150 Ft. | None |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from 3,915 feet to 145 feet. Set wooden plug at 145 feet.
Filled hole with $\frac{1}{2}$ sack of hulls and 15 sacks of cement to 96 feet. Filled with heavy mud to 40 feet and set wooden plug at 40 feet. Dumped $\frac{1}{2}$ sack of hulls on plug and filled to bottom of cellar with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
8/1/51
AUG 1 X 1951
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Barnett Drilling, Inc.
Address 623 First National Bank Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
W. E. Cruce (employee of owner) or (owner or operator) of the above-described well,
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. E. Cruce
623 First National Bank Building
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of July, 1951
Adelaide J. Olivier
Notary Public.

My commission expires May 12, 1955

PLUGGING
FILE SEC 36 T 9 R 20 4
BOOK PAGE 29 LINE 17

BARNETT DRILLING, INC., ET AL
LOG OF STEEPLES WELL NO. 1
SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$ SECTION 36-9S-20W, ROOKS COUNTY, KANSAS

DATE COMMENCED: July 14, 1951

DATE COMPLETED: July 28, 1951

| Formation | From | To | Remarks |
|----------------------|--------|--------|--------------------------------------------------------------|
| Surface Shale & Sand | 0 | 100' | Set 8 5/8" Surface Pipe @ 150 feet; cemented with 125 sacks. |
| Shale | 100' | 150' | |
| Shale | 150' | 575' | Dry and abandoned. |
| Shale and Shells | 575' | 895' | |
| Sand and Shells | 895' | 985' | |
| Shale and Shells | 985' | 1,080' | |
| Sand and Shells | 1,080' | 1,340' | |
| Shale and Shells | 1,340' | 1,440' | |
| Shale | 1,440' | 1,675' | |
| Anhydrite | 1,675' | 1,715' | |
| Shale and Shells | 1,715' | 2,455' | |
| Lime | 2,455' | 2,525' | |
| Lime and Shale | 2,525' | 2,725' | |
| Lime | 2,725' | 2,785' | |
| Shale and Shells | 2,785' | 2,890' | |
| Shale and Lime | 2,890' | 3,465' | |
| Lime | 3,465' | 3,870' | |
| Lime and Chert | 3,870' | 3,915' | |

Certificate

I, W. E. Cruce, of Barnett Drilling, Inc., hereby certify that to the best of my knowledge and belief, the above is a true and correct log of the Steeples Well No. 1, located in the SW $\frac{1}{4}$ SW $\frac{1}{4}$ NE $\frac{1}{4}$ of Section 36-9S-20W, Rooks County, Kansas.

W. E. Cruce

Subscribed and sworn to before me, in and for the County of Sedgwick, State of Kansas, this 31st day of July, 1951.

Delaine Olivier
 Notary Public

My Commission Expires: May 12, 1955

PLUGGING
 FILE 36-9-20W
 WORK PAGE 99 LINE 17

RECEIVED
 AUG 1 X 1951
 CONSERVATION DIVISION
 Wichita, Kansas