

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 2/89

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-23,088 (of this well).
(This must be listed; if no API# was issued, please note drilling completion date.)

WELL OWNER/OPERATOR Bankoff Oil Company OPERATOR'S LICENSE NO. 5422

ADDRESS P. O. Box 700657, Tulsa, OK 74170 PHONE # (316) 262-2784

LEASE (FARM) Neil WELL NO. 4 WELL LOCATION C S/2 N/2 N/2 COUNTY Rooks

SEC. 20 TWP. 9S RGE. 20 (~~E)XXX(W)~~ TOTAL DEPTH 3880' PLUG BACK TD

Check One:

OIL WELL GAS WELL D & A X SWD or INJ WELL DOCKET NO.

SURFACE CASING SIZE 8 5/8" SET AT 270.08' CEMENTED WITH 150 SACKS

CASING SIZE SET AT CEMENTED WITH SACKS

PERFORATED AT

CONDITION OF WELL: GOOD X POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING Circulate heavy mud in hole. 1st plug at 1718' w/25 sx. 2nd

plug at 1060' w/100 sx. 3rd plug at 300' w/40 sx. 4th plug at 40' w/10 sx. All cement

60/40 pozmix, 6% gel, 2 sx. Cello Flake.

(If additional space is needed use back of form.)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? No IS ACO-1 FILED? No
(If not explain.) Sent to operator for completion

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN at 9:30 a.m. on 04-01-90

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE
RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Anthony Martin PHONE # (913) 743-5443

ADDRESS 533 N. Main, Wakeeney, KS 67672

PLUGGING CONTRACTOR Abercrombie Drilling, Inc. LICENSE NO. 5422

ADDRESS 150 N. Main, Suite 801, Wichita, KS 67202 PHONE # (316) 262-1841

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT.

SIGNED: Jack K. Wharton
(Operator or Agent)

DATE: 05-03-90

4
STATE CORPORATION COMMISSION
WICHITA, KANSAS
MAY 07 1990