

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 6/4/84

15-163-19340-00-01

WELL PLUGGING APPLICATION FORM  
(File One Copy)

API NUMBER Drilled Aug. 1950 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Production Management, Inc. OPERATORS LICENSE NO. 6234

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202 PHONE # (316) 265-4651

LEASE (FARM) Copeland WELL NO. 6 WELL LOCATION SW SE NW COUNTY Rooks

SEC. 19 TWP. 9S RGE. 20 (X) or (W) TOTAL DEPTH 3832 PLUG BACK TD 3832

Check One:

OIL WELL  GAS WELL \_\_\_\_\_ D & A \_\_\_\_\_ SWD or INJ WELL \_\_\_\_\_ DOCKET NO. \_\_\_\_\_

SURFACE CASING SIZE 10 3/4 SET AT 275 CEMENTED WITH 250 SACKS

CASING SIZE 7 SET AT 3821 CEMENTED WITH 200 SACKS

PERFORATED AT LKC - 3542-3738', Arbuckle - open hole

CONDITION OF WELL: GOOD \_\_\_\_\_ POOR \_\_\_\_\_ CASING LEAK  JUNK IN HOLE \_\_\_\_\_

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run tbg. & circ. clean to td. Pump 90 sx. 65-35 Poz, 10% gel & hulls to fill 500' OB. Pick up to 3250' & pump 55 bbls. gel mud. Pick up to 1850' & perf. Pump 135 sx. Pick up to 1050' & perf. Pump 220 sx. to circ. to surf.

(If additional space is needed use back of form)

POOH. Squeeze 7" w/75 sx. Pump 100 sx. dn annulus.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no

(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Park

PHONE # (316) 265-4651

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202

PLUGGING CONTRACTOR B-J Titus LICENSE NO. \_\_\_\_\_

ADDRESS Hays, Kansas PHONE # (913) 625-3019

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steve Park

(Operator or Agent)

DATE: 5-11-90

9

RECEIVED  
STATE CORPORATION COMMISSION  
5/14/90  
CONSERVATION DIVISION  
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN	GOVERNOR
KEITH R. HENLEY	CHAIRMAN
RICH KOWALEWSKI	COMMISSIONER
JACK SHRIVER	COMMISSIONER
JUDITH MCCONNELL	EXECUTIVE DIRECTOR
FRANK A. CARO, JR.	GENERAL COUNSEL

CONSERVATION DIVISION  
 SHARI FEIST ALBRECHT, DIRECTOR  
 200 Colorado Derby Bldg.  
 202 W. 1st Street  
 Wichita, KS 67202-1286  
 (316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 30, 1990

Petroleum Production Management, Inc.  
 209 E. William, Suite 200  
 Wichita, KS 67202

Copeland #6  
 SW SE NW 19-09-20W  
 Rooks County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely,

*David P. Williams*

David P. Williams  
 Production Supervisor

District: #4, 2301 E. 13th  
 Hays, KS 67601  
 (913) 628 - 1200