

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

15-163-02247-00-26

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER Drilled Oct. 1949 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Production Management, Inc. OPERATORS LICENSE NO. 6234

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202 PHONE # (316) 265-4651

LEASE (FARM) Copeland WELL NO. 3 WELL LOCATION SW SW NW COUNTY Rooks

SEC. 19 TWP. 9S RGE. 20 (E) or (W) TOTAL DEPTH 3946 PLUG BACK TD 3891

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 485 ^{KCC ZAP} 495 CEMENTED WITH 250 SACKS

CASING SIZE 5 1/2 SET AT 3938 ^{KCC ZAP} 3944 CEMENTED WITH 250 SACKS

PERFORATED AT LKC 3545-3740', Arbuckle 3840-3842'

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run tbg. & circ. clean to PBD. Pump 55 sx. 65-35 Poz. 10% gel & hulls to fill up 500" OB. Pick up to 3400' & pump 33 bbls. gel mud. Pick up to 1850 & perf. 3 holes. Pump 80 sx. Pick up to 1050 & perf. Pump 110 sx to circ. to surf.

(If additional space is needed use back of form)

POOH. Squeeze 5 1/2" w/75 sx. Pump 50-75 sx. dn annulus.
IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? no
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Park

PHONE # (316) 265-4651

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202

PLUGGING CONTRACTOR Wichita LICENSE NO. _____

ADDRESS Hays, KS PHONE # (913) 625-3019

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steve Park
(Operator or Agent)

DATE: 5-11-90

(4)

RECEIVED
STATE CORPORATION COMMISSION
5/14/90
CONSERVATION DIVISION
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
JACK SHRIVER COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

NOTICE OF RECEIPT OF
WELL PLUGGING APPLICATION

July 30, 1990

Petroleum Production Management, Inc.
209 E. William, Suite 200
Wichita, KS 67202

Copeland #3
SW SW NW 19-09-20W
Rooks County, KS

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
Production Supervisor

District: #4, 2301 E. 13th
Hays, KS 67601
(913) 628 - 1200