

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM
(File One Copy)

API NUMBER 15-163-20,602 - 00-00 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Petroleum Production Management, Inc. OPERATORS LICENSE NO. 6234

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202 PHONE # (316) 265-4651

LEASE (FARM) Copeland WELL NO. 10 WELL LOCATION SE SW NW COUNTY Rooks

SEC. 19 TWP. 9S RGE. 20 (E) or (W) TOTAL DEPTH 3814 PLUG BACK TD 3814

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 223 CEMENTED WITH 160 SACKS

CASING SIZE 5 1/2 SET AT 3813 CEMENTED WITH 550 SACKS (2 54a.)

PERFORATED AT Open hole

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Run tbg. & circ. clean to TD. Pump 55 sx. 65-35 Poz, 10% gel & hulls to fill 500' OB. Pick up to 3300' & pump 33 bbls. gel mud. Pick up to 1830' & perf. Pump 80 sx. Pick up to 1050' & perf. Pump 110 sx. to circ. to surf. P00H.

(If additional space is needed use back of form)

Squeeze 5 1/2" w/75 sx. Pump 50-75 sx. dn annulus.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? yes IS ACO-1 FILED? yes
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Steve Park PHONE # (316) 265-4651

ADDRESS 209 E. William, Suite 200, Wichita, KS 67202

PLUGGING CONTRACTOR B-J Titan LICENSE NO. _____

ADDRESS Hays, KS PHONE # (913) 625-3019

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: Steve Park
(Operator or Agent)

DATE: 5-11-90

(4)

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1990
CONSERVATION DIVISION
Wichita, Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
 KEITH R. HENLEY CHAIRMAN
 RICH KOWALEWSKI COMMISSIONER
 JACK SHRIVER COMMISSIONER
 JUDITH MCCONNELL EXECUTIVE DIRECTOR
 FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
 SHARI FEIST ALBRECHT, DIRECTOR
 200 Colorado Derby Bldg.
 202 W. 1st Street
 Wichita, KS 67202-1286
 (316) 263-3238

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

July 30, 1990

Petroleum Production Management, Inc.
 209 E. William, Suite 200
 Wichita, KS 67202

Copeland #10
 SE SW NW 19-09-20W
 Rooks County, KS
 API No. 15-163-20,602

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). Failure to do so is punishable by an administrative penalty of up to \$1000.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams

David P. Williams
 Production Supervisor

District: #4, 2301 E. 13th
 Hays, KS 67601
 (913) 628 - 1200