



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

5/17/72

Dear Sir:

Mr. Bob Wynn of Gabbert-Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Wynn guarantees payment of the plugging fee.

Operator's full Name: James W. Thompson,

Complete Address: 355 R. H. Garvey Building, Wichita, Kansas.

Lease Name: Desbien Well No. 1

Location: SE-NE-SW Sec. 3 Twp. 9 Rge. (E)(W) 21

County: Graham Total Depth 3702' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Wynn was instructed to plug the well as follows:

282'--8 5/8" Surface casing, cement circulated with 160 Sx.
Top of Dakota section @ 575'.

Circulate hole with heavy mud. Pull DP to 800' and displace 110 Cu. Ft. cement thru DP. Pull DP to 310' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

A. L. Pichok
Conservation Division Agent