



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 30 1974  
12-30-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name R. P. Nixon Operations

Complete Address Box 589, Russell, Kansas 67665

Lease Name Paul Miller Well No. 1

Location SE NE NW Sec. 18 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3822'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Crowe Casing Pulling

Address Box 706, Hays, Kansas 67601 License No. 733

Operation Completed: Hour 11:15 A Day 26 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 3822' 8 5/8 csg set at 279' cwc

5 1/2 csg set at 3760' cw 100 sx cem.

Set 5 1/2 wood plug at 1600' -dumped 5 sk cem. W/dump bailer. (1600-1565)

Cutoff & recovered 1320' of 5 1/2 csg.

Mixed & pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk 50-50 poz

6% -10 sk gel & water -released 8 5/8 plug & 50 sk 50-50 poz 6% by Sun Cem. Co.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED

DATE 12/31/74

INV. NO. 546-W