

KANSAS

Form CP-3
Rev. 6-4-68

R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1976
12-28-76
CONSERVATION DIVISION
WICHITA, KANSAS

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -163 -20,649-00-00 (of this well)

Operator's Full Name Southern States Oil Co.

Complete Address Box 1365, Great Bend, Kansas

Lease Name Lambert Well No. 2

Location SE NW NE Sec. 29 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3915'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Duke Drlg.

Address Great Bend, Kansas License No.

Operation Completed: Hour 4:30 P Day 22 Month 12 Year 1976

The above well was plugged as follows:

RTD 3915' 8 5/8 csg set 263' cwc 160 sx. Plg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid

bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Marouf
Well Plugging Supervisor

INVOICED

DATE 12-29-76

INV. NO. 4389-W