

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
6-14-71
JUN 14 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Petroleum, Inc.

Complete Address R. R. # 2 Great Bend, Kansas 67530

Lease Name Kern "D" Well No. 1

Location SE SW NE Sec. 29 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3896

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 12 N Day 9 Month 6 Year 1971

The above well was plugged as follows:

Total Depth 3896' 8 5/8 csg set at 231' cwc 175 sk.

5 1/2 csg set at 3895' cw 75 sk cmt.

5 1/2 csg PBTID 3892 with perf. (3889-3891)

Filled 5 1/2 csg W/sd (3800-3892) Dumped 5 sk cmt W/dump bailer. (3765-3800)

Cutoff and recovered 2000' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel W/5 sk hulls, -70 sk poz 60 -50 6% -12 sk gel -

release plug and pumped 50 sk poz 6%. Max pres 250 lbs. SI pres. 150 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey
Well Plugging Supervisor

INVOICED
DATE 6-14-71
INV. NO. 3854-W