

15-163-01766-00-00

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
CONFIRMATION COMMISSION
DEC 8 1966
12-8-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Nadel & Gussman

Complete Address: P. O. Box 158 Plainville, Kansas

Lease Name Kern Well No. 4

Location NW SE SW Sec. 28 Twp. 9 Rge. 20 (E) (W) X

County Rooks Total Depth 3863

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Forbes Casing Pulling

Address: Great Bend, Kansas License No. 49

Operation Completed: Hour 2:15 PM Day 6 Month 12 Year 1966

The Above well was plugged as follows:

Total Depth 3863' 8 5/8 csg set at 150' cwc 110 sc.

5 1/2 csg set at 3861' cw 125 sc cement.

Sand back to 3830' - Dumped 5 sc cement with dump bailer.

Recov. 1250' of 5 1/2 csg.

Squeezed 8 5/8 csg with 18 sc gel and 70 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 12/9/66
INV. NO. 4420-W