

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE NE SE

SEC. 28 TWP. 9 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-B Lease Sutor 204 1002

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 5841 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 250' circulated with cement - 5 1/2" at 3839' with
90 sax cement behind.

Dumped 5 sax cement in bottom with dump bailer - pulled
1364' 5 1/2" - pumped in 90 sax Aquagel with 10 sax hulls, filling
hole with mud to 250', set rock bridge and 15 sax cement,
filled with mud to 35', set rock bridge and 10 sax cement
to bottom cellar.

5-31-51
MAY 31 1951

CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent

Date 5-30-51

PLUGGING
FILE SEC 28 T 9 R 20
BOOK PAGE 85 LINE 21