

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 163-21, 103-00-00 (Well)

Operator's Full Name FRONTIER OIL COMPANY

Complete Address 1720 N.S.B. BLDG. - WICHITA, KANSAS, 67202

Lease Name RENNER Well No. #1

Location Q- E 1/2 - E 1/2 - SE Sec 28 fwp. 9 Rge. 20 (E) (W) W

County ROOKS Total Depth 3855 FE

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor RED TIGER DRUG CO.

Address 1720 N.S.B. BLDG. WICHITA, KS. License No. _____

Operation Completed: Hour 10:00 PM Day 18th Month JULY Year 1980

The above well was plugged as follows:

8 5/8" 250 FE SP. CUC. W/250 ST COMMON 2% GEL - 3% CA-CL
ORDERED 110 ST 50/50 PZMIX 6% GEL + 8 5/8 PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1ST PLUG. @ 860 FE W/70 ST CMT.

2ND PLUG. @ 240 FE W/25 ST CMT.

3RD PLUG. -> SOLID BRIDGE HULLS PLUG. @ 40 FE TO 0 W/10 ST CMT.

5TH IN RAT HOLE

CEMENTED BY ALLIED CMT.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Mason Schmidt
Well Plugging Supervisor

INVOICED
DATE 7-25-80
INV. NO. 2680-W
JUL 22 1980
7-22-80
CONSERVATION DIVISION
Wichita, Kansas