

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 140-46
LOCATION SE NE NE
SEC. 28 TWP. 9 RGE. 20 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Brightonstein

Operator I. O. Miller Address 619 Brown Bldg Wichita, Kans

Field _____ County Rooks

Total Depth 3800 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____
(Describe briefly the manner in which the well was plugged)

8 5/8" at 215' circulated with cement - 5 1/2" at 3859' with 75 sax
cement behind.

Filled with chat to 3840', set 4 sax cement with dump bailer - pulled
3300' 5 1/2" - pumped hole full mud (40 sax Gel) - pumped cementing
plug to 215', followed by 70 sax cement - Cement 215' to 0'.

Mudding and cementing by Globe Cementing Co.

District Conservation Agent

Date 29

RECEIVED
STATE CORPORATION

3-12-57

PLUGGING
FILE SEC 28 T 9 R 20 W
BOOK PAGE 140 LINE 43