

R

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

*Handwritten:* JUN 07 1977  
6-7-77  
CHAS. H. ...  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 163 - 20,698 - 00 - 00 (of this well)

Operator's Full Name Helberg Oil Co.  
Complete Address Box 32, Morland, Kansas  
Lease Name J. Kern Well No. 1  
Location 1220' EWL & 660' SNL of SW/4 *App. N/2 SW* Sec. 28 Twp. 9 Rge. (E) (W) 20  
County Rooks Total Depth 3908'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Co. Tools  
Address        License No.         
Operation Completed: Hour 3 A Day 4 Month 6 Year 1977

The above well was plugged as follows:

RTD 3908' @ 5/8 csg set 200' cwc Plg Mat 50-50 poz 6% total gel.  
Gunned pits, circulated heavy mud, set 70 sk cmt plug at 720' thru drill pipe.  
Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 6-7-77

INV. NO. 5290-W