

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

Rev. 6-4-68

RECEIVED  
STATE CORPORATION COMMISSION

5/16/77  
MAY 16 1977

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas

API Number 15 - 163 - 19102 - 00 - 01 (of this well)

Operator's Full Name C & W Oil Co.

Complete Address Box 163, Ellis, Kansas 67637

Lease Name Hinkhouse (OWWO) Well No. 1

Location SW SW SW Sec. 33 Twp. 9 Rge. (E) (W) 20

County Rooks Total Depth 3840'

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Co. Tools by Allied Cementing Co.

Address        License No.       

Operation Completed: Hour 12 N Day 14 Month 5 Year 1977

The above well was plugged as follows:

Total Depth 3840' 10 3/4 csg set 240' cwc

6" csg set 3840' cw 150 sk cem.

6" csg PBTD 3550' with perf. (3310'-3320')

6" csg squeezed thru Dakato & circulated to surface. No pipe recovered.

Allied Cementing Co. mixed & pumped down 6" csg with 35 sk cem. -displaced with

25 sk gel & water W/500 lbs hulls -capped with rubber plug & 90 sk cem. & shutin.

PP 400 lbs.

I hereby certify that the above well was plugged as herein stated.

Signed: Bob Massey  
Well Plugging Supervisor

5/16/77

INV. NO. 5158-W