

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE SE SW

SEC. 33 TWP. 9 RGE. 20^W

Dry Hole _____ Abandoned Oil Well x Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease Marcotte

Operator Lohman-Johnson Address Hays, Kans

Field _____ County Rooks

Total Depth 3850 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 340' circulated with cement - 5 1/2" at 3848' with
100 sax cement behind - perforated at 3563' and squeezed with
150 sax cement.

Filled with sand and cement to 3625', set bridge at 3530' with
4 sax cement, pulled 3063' 5 1/2", filled hole with md to
250', set rock and 15 sax cement, filled with md to 35', set rock
and 10 sax cement to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
9/20/51
SEP 20 1951

District Conservation Agent

Date 9-16-51

PLUGGING
FILE SEC 33 T 9 R 20^W
PAGE 100 LINE 31

CONSERVATION DIVISION
Wichita, Kansas