



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 93-18

LOCATION NW SW SW

SEC. 33 TWP. 9 RGE. 20

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1-A Lease Marcotte

Operator Lohmann-Johnson Address c/o Harold Dorset
2105 Milner Great Bend.

Field _____ County Rooks

Total Depth 3839 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 350' circulated with cement. 5 1/2" at 3837' with 200 sax
cement behind.

Sand to 3595' - tubing cut off at 3595' - set 4 sax cement at
3595' with dump bailer - pulled 1200' 5 1/2" - filled with mud to
350', set rock and 10 sax cement, mud to 35', set rock and 10 sax
cement to bottom cellar.

PLUGGING

FILE NO. SEC 33 T 9 R 20
PAGE 93 LINE 18

STATE CORPORATION COMMISSION
APR 25 1933
CONSERVATION DIVISION
Wichita, Kansas

Edward J. [Signature]
District Conservation Agent
Date 4-21-33