

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-143 - 01722-00-90

SW-SW. SE, Sec. 18, T 9 S, R 20 E

330 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6237

Lease Name JOHN TOWN'S Well # 1

Operator: GETTY OIL COMPANY
Name & Address BOX 3000
TULSA, OKLAHOMA
74102

County ROOMS.

Well Total Depth 3785 feet 123.01

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor ALLIED CEMENTING License Number 913-483-2627

Address BOX 31 RUSSELL, OKLA. 67665

Company to plug at: Hour: 10:00 AM Day: 14 Month: MARCH Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO ED BRAUN

(company name) GETTY OIL CO. (phone) 918-560-6300

were: 8 5/8" - 290' @ 100' cont. -> 5 1/2" SET @ 3783' @ 250' cont.

TEMP SERVICE @ 2530' - PERFS - 3783' to 85' - HOLES @ 1302' - 1445'

AND 850' - SANDED IN @ BOTTOM TUBING RODS AND PUMP @ 2381'

ORDERED 350' 5 1/2" FORMIN 6% GEL - 3% CA-CL, 3" GEL, 3" HULLS, 8 5/8" PLUG

PUMP IN WITH PUMP TOUCH, RETURNED FOR ADDITIONAL 150' 5 1/2"

FORMIN 4% GEL - 3% CA-CL AND 8" HULLS. Signed M. Schmidt (TECHNICIAN) DOIC

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:45 PM Day: 14 Month: MARCH Year: 19 83

ACTUAL PLUGGING REPORT ORDERED 350' 5 1/2" FOR 6% GEL - 3% CA-CL,

3" GEL, 3" HULLS, AND 8 5/8" PLUG. SPOTTED WITH TUBING

SPOTTED WITH TUBING 25' cont @ 2340' FE, AND 3" GEL.

SPOTTED 80' cont @ 1765' FE AND 2" HULLS, SPOTTED 100' cont @ 850' FE

RETURNED FOR ANOTHER 150' cont + 8" HULLS. - PUMPED IN 5 1/2" CSE

ANOTHER 160' cont w/ 3" HULLS AND 25' of CELLO-FLAME MIX. PRESSURE

450 PSI SHUT IN AT 300 PSI. REMARKS: PUMPED 90' IN ANNULUS AND 1" HULLS. MAX PSI 600 LBS.

CEMENTED BY ALLIED OIL.

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

INVOICED
DATE 4-13-83
INV. NO. 3968-W

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1983
3-28-83
CONSERVATION DIVISION
Wichita, Kansas

Signed M. Schmidt (TECHNICIAN) DOIC

FORM CP-2/3
Rev. 9-82